



3205 US-23 South
Alpena, MI 49707
Ph: 989-356-6375
Fax: 989-354-8286

September 7, 2023

***Lake Manuka Road
Addendum #1***

This Addendum is issued for the purpose of modifying and/or clarifying the original drawings and specifications and shall take precedence over them.

All work included herein shall be in accordance with the original drawings and specifications except as specifically noted herein. All incidental items required to provide the following modifications shall be included even though not specifically described.

It shall be the responsibility of the contractors to notify their subcontractors and/or suppliers of the clarifications, modifications, and/or revisions included herein.

Receipt of this Addendum shall be noted on the Itemized Bid Sheet.

The following project clarifications are provided based on questions received:

1. The log for this project originally contained Aggregate Base Conditioning, this project is an HMA wedge and overlay project with gravel shoulders. Attached is a revised Log of Project and Blank Bid Sheet.

LOG OF PROJECT

Lake Manuka Road, Hayes Township, Otsego County, Michigan.

DESCRIPTION OF WORK

The project includes HMA wedge and overlay for approximately 1100 feet. Project is located at the following Coordinates.

Lat 44°57'3.29" N
Long 84°44'35.73" W

MISCELLANEOUS ITEMS OF WORK

| | | |
|--------------------|---|------|
| Mobilization, Max. | 1 | LSUM |
| Minor Traf Devices | 1 | LSUM |

MAINLINE

Place 220 lb/syd of HMA at a 2% cross slope, this may require a wedging course (12' lane width for a total of 24' width), and aggregate shoulders (2' width each side).

| | | |
|-----------------------|-----|-----|
| Shld, CI II, Modified | 100 | Ton |
| HMA 4EL | 500 | Ton |

DRIVEWAYS

| | | |
|-----------------------|----|-----|
| Shld, CI II, Modified | 25 | Ton |
|-----------------------|----|-----|

GENERAL PLAN NOTES

The improvements in this proposal shall be done in accordance with the Michigan Department of Transportation's 2020 MDOT Standard Specifications for Construction, Supplemental Specifications and the attached Special Provisions.

STANDARD PLANS

Where the following items are called for, they are to be constructed according to the Standard Plan listed below unless otherwise indicated.

Traffic and Safety Special Details

- *WZD-100-A Ground Driven Supports for Temp Signs
- *WZD-125-E Temporary Traffic Control Devices

Schedule of Items (Itemized Bid Sheet)

Letting Date: Monday, September 11, 2023 9:00 AM

Contract ID: 23.025 Manuka
Location: Lake Manuka Rd Hayes Twp Otsego Co
Description:

| | |
|---|---|
| Project Number: 23.025 Manuka | Project Engineer: REBECCA RIVARD |
| Estimate Number: 1 | Date Created: 8/22/2023 |
| Project Type: Miscellaneous | Fed/State #: |
| Location: Lake Manuka Rd Hayes Twp Otsego Co | Fed Item: |
| | Control Section: |

Description:

Instructions to Bidders: IMPORTANT NOTICE:
If the proposal establishes a maximum price for any of the following work items, and if you bid a price higher than that maximum price, your bid will be considered to have quoted the maximum price and your bid total will be adjusted to reflect that maximum price.

If the proposal provides a specified price for any of the following work items, and if you bid a price higher or lower than that specified price, your bid will be adjusted to reflect that specified price.

If your bid is the lowest accepted bid, and if you refuse to accept the award of the contract due to the change in what you quoted as a maximum or specified price, you will forfeit your proposal guaranty.

| Pay Item | Description | Quantity | Units | Unit Price | | Bid Amount | | |
|-------------------|-------------------------|----------|-------|------------|-----|------------|-----|--|
| | | | | Dollars | Cts | Dollars | Cts | |
| 1100001 | Mobilization, Max | 1 | LSUM | | | | | |
| 3027031 | _ Shld, CI II, Modified | 125 | Ton | | | | | |
| 5012024 | HMA, 4EL | 500 | Ton | | | | | |
| 8120170 | Minor Traf Devices | 1 | LSUM | | | | | |
| Total Bid: | | | | | | | | |

Contractor: _____

(Signature)

(Date)